BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule-B

NAME OF THE WORK: Construction of RCC drain and Improvements to road at Grape Garden Main road T. Dasarahalli ward no 15

Sl. No	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in Hard Soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 9 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per the direction of Engineer-in-charge of the work	cum	601.20	208.82	Rupees Two Hundred Eight and Eighty Two Paise Only
2	: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, including cost of all materials, labour HOM of machinery curing complete as per specifications	cqm	90.18	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only
3	Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser	cum	202.90	6965.26	Rupees Six Thousand Nine Hundred Sixty Five and Twenty Six Paise Only
4	Supplying, fitting and placing TMT bar Fe 500 reinforcement	ton	12.17	66482.14	Rupees Sixty Six Thousand Four Hundred Eighty Two and Fourteen Paise Only
5	Providing and removing centering, shuttering, strutting, propping etc;. And removal of form work for vertical surface such as walls at any thickness, includig attached pilasters, butresses, plinth cills and string courses cost of all material	sqm	1803.60	310.58	Rupees Three Hundred Ten and Fifty Eight Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BRND DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

6	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mmc/c bothways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials	sqm	450.90	1698.00	Rupees One Thousand Six Hundred Ninety Eight Only
7	Providing and fixing Pre cast solid cement concrete kerb stones made out of No272.21 C.C 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc	No.s	1055.00	331.78	Rupees Three Hundred Thirty One and Seventy Eight Paise Only
8	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications	sqm	213.64	63.60	Rupees Sixty Three and Sixty Paise Only

EXECUTIVE ENGINEER-4
DASARAHALLI DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP